



## **ITEM 9000-0003 CEMENT CONCRETE CURB RAMP**

**DESCRIPTION** – This work is the construction of ADA Curb Cut Ramps as indicated in SC-502a through SC-502-i in the City of Pittsburgh Standards of Construction, Appendix B of the Right-of-Way Procedures Policy Manual (current edition).

**MATERIAL** – In accordance with PennDOT Publication 408, Section 676.2, except add the following:

- Class AA Cement Concrete – In accordance with PennDOT Publication 408, Section 704, except must have a 28-day compressive strength of 4000 psi.
- Welded Wire Fabric, 6 x 6 x W4.0 x W4.0 – In accordance with PennDOT Publication 408, Section 709.

**CONSTRUCTION** – As shown in SC-502a through SC-502i of the City of Pittsburgh Standards of Construction, Appendix B of the Right-of-Way Procedures Policy Manual (current edition).

Construct expansion joints as indicated in SC-502a through SC-502i of the City of Pittsburgh Standards of Construction. Joints are incidental to the ADA Curb Cut Ramp.

### **MEASUREMENT AND PAYMENT –**

- (a) **ADA Curb Cut Ramp.** Square Yard. Boiled Linseed Oil is incidental. If depressed curb is placed monolithically with curb ramps, side-flairs, or both, the depressed curb will be measured and paid separately from curb ramps and side flairs.
- (b) **Class 1A Excavation.** Cubic Yard
- (c) **Class 1B Excavation.** Cubic Yard
- (d) **Detectable Warning Surface.** Square Feet

**END OF SPECIAL PROVISION**